ENGINEERING DEPARTMENT.

WATER-SUPPLY CONSTRUCTION DIVISION, BANGALORE.

Notification dated 13th March 1925.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Water-Supply Construction Division, up to 2 P.M. of 6th April 1925, for providing a Latrine and Sanitary Fittings to the Bangalore New District Office Buildings converted into Science Laboratory attached to Central College. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1925.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore, between the hours of 11 A.M. and 5 P.M., on all working days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed:—

Description of work	Unit of work	Rate per unit

4. Each tender must be accompanied by a deposit of Rs. 200 (two hundred) only in cash as earnest money, and be superscribed "Tender for providing a Latrine and Sanitary Fittings to the New District Office Buildings at Bangalore" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Charges on account of scaffolding materials, implements for setting out, barricading, clearing site, supply of water, etc., that may be found necessary during execution will not be paid for separately but should be borne entirely by the contractor.

10. Rates for none-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not morethan 10 per cent for contractor's profit.

11. In all matter not specifically provided for, and in all matters of disputes about rates, quantities, measurements, quality of work, etc., and in all disputes of any kind, the decision of the Chief Engineer of Mysore, will be final and legally binding.

Abstract of Quantities.

Serial No.	Description of work	Unit of work	Quantity
	CONSTRUCTING A BUILDING FOR CLOSET, URINALS AND LAVATORY.		
1	Earthwork excavation	C.yds.	11
2	Surki concrete in foundation	C.ft.	390
3	Burnt stone in mortar	,,	214
4	Burnt brick in mortar	,,	600
5	Burnt stone slabs 6" thick one line dressed	Sq.ft.	71
6	Cement pointing to basement	Sq.	1·04
7	Earthwork filling, forming, watering and tamping	C.yds.	7
8	Plastering with cement ½" thick (1 to 3)	Sq.	5·79
9	Do mortar do	,,	7·25
10	Coping brick in mortar and plastering	R.ft.	38
11	Teakwood work including wood oiling	C.ft.	10·41
12	Roofing with Bengal terrace including teakwood reepers 2" x 1"	Sq.	1·64
13	Teakwood ventilators with expanded metal, complete	S.ft.	9
14	Teakwood panelled door, complete	,,	26
15	Do battened shutters in 1" plank including hinges, bolts, etc., complete without frame.	,,	60
16	Eave board plain 9" teakwood	R.ft.	57
17	Chocolate painting to wood work	Sq.	2·67
18	Flooring with Cuddapah slab on 3" concrete and cement pointing ..	,,	2·35
19	1½" Cudappa slab partition including cement pointing, dressing and rounding edges and fixing.	,,	0·93
20	Whitewashing two coats	,,	4·00
21	Colorwashing one coat	,,	4·00
22	Constructing squatting urinals complete with surki concrete and cement plastering.	No.	2

Serial No.	Description of work	Unit of work	Quantity
	SANITARY CONVENIENCES.		
23	Fixing Hindustani Closets with fittings, complete	No.	4
24	Fixing English do do ..	,,	1
25	Fixing single person basin urinals do	,,	2
26	Fixing one set of three persons range urinals with Cuddapah slab fittings, etc., complete.	,,	1
27	Fixing Lavatory with fittings, complete	,,	1
28	Fixing zinc cowel	,,	1
29	Constructing 6" x 4" gully trap cistern including fixing C. I. frame grating, complete.	,,	1
30	Constructing field's flushing tank of 50 gallons capacity not including the cost of the flushing syphon	,,	1
31	Laying and jointing 4" S. W. channel pipes including cutting and fixing in cement.	R.ft.	14
32	Laying and jointing 6" S. W. pipes including cutting and fixing in cement ..	,,	20
33	Do 4" do do ..	,,	10
34	Fixing 6" x 4" S. W. junction with cement	No.	6
35	Fixing 1½" lead pipes lavatory including making joints, etc., complete ..	R.ft.	6
36	Fixing 4" Wrought iron Ventilating Shaft of 16 feet height including cost of making connection to the drain and constructing a masonry support, cement plastered alround.	No.	1
	LAYING PIPE SEWERS FOR THE LATRINE.		
37	Earthwork excavation and refilling, watering, tamping and forming for the pipe line, complete.	C.yds.	554
38	Soft rock excavation do do ..	,,	277
39	Hard rock do do do ..	,,	277
40	Laying and jointing 6" S. W. pipes with cement	R.ft.	1,788
41	Fixing 6" S. W. bend and junction	No.	2
42	Laying and jointing 6" S. W. channel pipes in manholes with cement joints including cutting, etc., complete.	R.ft.	32
43	Constructing Manholes of size 4' x 4' with brick in surki mortar walls, 9" thick and a surki concrete bed 5½' x 5½' including the foundation of walls and surki concrete sloping sides on both sides of the open channel in the manhole, plastering with cement mortar (1 to 3) ½" thick to the bed and sides of manhole up to the top including rounding of edges and corners in cement mortar, fixing 6" burnt stone covering slabs (5½' x 5½') cutting groove in the slab and fixing manhole cover and frame in cement and fixing C. I. steps in the manhole where necessary (including cost of materials except cast iron manhole frame and cover and cast iron steps) of the following depths :—		
	3' deep	No.	1
	3½' ,, ...	,,	1
	4' ,, ...	,,	2
	4½' ,, ...	,,	2
	7' ,, ...	,,	1
	7½' ,, ...	,,	1
44	Repairing road crossing after refilling the trench including metalling and consolidation and barricading for 30 R. ft.	,,	1

H. F. MARKER,
Executive Engineer,
Special Water-Supply Construction Division.

BHADRAVATI DIVISION.

TIMBER SALE.

Abstract Notification.

The attention of the public is invited to the detailed notification regarding the auction sale of timber in the Bhadravati and Tarikere Depots of this Division on 6th April 1925 and 8th April 1925, respectively, published on pages 201, 202, Part VI of the *Mysore Gazette* dated 12th March 1925.

M. MACHAIYA,
District Forest Officer.

OFFICE OF THE EXECUTIVE ENGINEER, MYSORE DIVISION.

Notification dated Mysore, 11th March 1925.

It is hereby notified for the information of the public that the 2nd class travellers' bungalow at Mandya, will temporarily be closed for occupation by the intending travellers for two months with effect from the 20th March 1925, when it will be under repairs.

The date of reopening of the same for occupation by the public will duly be notified.

L. A. H. WINCKLER,
Executive Engineer.